BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/12/2022-23 Dated: 26-08-2022

APPROVED TENDER SCHEDULE –'B'

Item 27

Name of Work:-Improvements to Roads and drains in susheelamma layout and ISAAC layout in Chowdeshwari ward no -02 of yelahanka Sub division.

	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri.RAMESH Y B	
				Rate	Rate in Words
	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work	Cum	101.50	62.92	SixtyTwo Paise NinetyTwo Only
	Construction of Granular Sub-Base of required grading as per design mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401	Cum	43.50	2271.90	Two Thousand Two Hundred SeventyOne Paise Ninety Only
3	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical	Cum	65.25	2317.39	Two Thousand Three Hundred Seventeen Paise ThirtyNine
4	Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.90 kg per m2 using mechanical means.	Sqm	290.00	40.66	Fourty Paise SixtySix Only
5	Providing and applying tack coat with VG-10 Bitumen using pressure distributor at the rate of 0.20 kg/m2on the prepared bituminous surface cleaned with mechanical broom	Sqm	1740.00	11.62	Eleven Paise SixtyTwo Only
6	Providing and laying Dense Graded Bituminous Macadam with 40/60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects.	Cum	14.50	8846.55	Eight Thousand Eight Hundred FourtySix Paise FiftyFive Only

Executive Engr
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE

	Providing and laying Bituminous Concrete with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects	Cum	69.60	9512.54	Nine Thousand Five Hundred Twelve Paise FiftyFour Only
8	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 g/ m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level, uniform and free from streaks and holes.	Sqm	58.00	462.70	Four Hundred SixtyTwo Paise Seventy Only
9	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km	m	129.92	92.93	NinetyTwo Paise NinetyThree Only

Signature of the
Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

Regd. & Head Office: MANGALURU - 575 002